



Republic of the Philippines  
**CAVITE STATE UNIVERSITY**  
 Don Severino delas Alas Campus  
 Indang, Cavite

## BILL OF QUANTITIES

REPAIR AND IMPROVEMENT OF ROLLE HALL ABC: 1,158,158.10 COLLEGE/UNIT/CAMPUS: MAIN CAMPUS		Bill of Quantities			
Item No.	Description	Unit	Quantity	Unit Price (Pesos)	Amount (Pesos)
I	MOBILIZATION (Pesos _____ _____ and _____ centavos)				
II	SCRAPING AND DISMANTLING WORKS (Pesos _____ _____ and _____ centavos)				
III	CARPENTRY WORKS (Pesos _____ _____ and _____ centavos)				
IV	PAINTING WORKS (Pesos _____ _____ and _____ centavos)				
V	ELECTRICAL WORKS (Pesos _____ _____ and _____ centavos)				
<b>GRAND TOTAL</b>					_____
<b>Write grand total in words</b>		_____ _____ _____			

Submitted by: \_\_\_\_\_ Date: \_\_\_\_\_  
 Name of Bidder/Bidder's Representative: \_\_\_\_\_  
 Position: \_\_\_\_\_  
 Construction Company/Contractor: \_\_\_\_\_

## **CAVITE STATE UNIVERSITY**

SCOPE OF WORK:

### **A. REPAIR AND IMPROVEMENT OF ROLLE HALL**

#### **GENERAL NOTES:**

1. The project should be finished in 45 calendar days.
2. There is an existing structure and verification of the actual site is a must.
3. The area should be cleared/cleaned before and after the construction work at least ten meters away from the building line. Unusable used formworks, excessive soil fill and all other unwanted debris of construction works should be disposed properly.

### **B. Technical Description**

#### **I. Mobilization**

- A. Site Preparation/ Temporary Enclosure/ Mobilization

- then spot coat with top coat.
2. Apply two coats of colored elastomeric paint or factory mixed dirt resisting semi-gloss latex.
  3. Apply two coats of Acqua Epoxy Primer on the flooring of the structure.
  4. This work includes repainting of flooring of the social hall with Acqua Epoxy Primer specifically the entrance and the main âe